

SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

No. 4963

Dated: 06/05/2025

It is certified that an inspection team headed by Sub Division Engineer, water Supply & Sanitation Sub Division Jalalabad (w) (Junior Engineers)

(Name of Officers with Designation) from PHED inspected the Glorious convent school,

Mandi Ladhuka, District: Fazilka, State: Punjab on 14-04-2025 (date of inspection) and on the basis of

Water Test Report (Attached) bearing no. DWT4/F2K/2496 dated 16-04-2025 of (PHED Lab) certified that the Glorious convent School has safe

drinking water facilities for the students and members of staff of the institution. School is also maintains the hygienic sanitation condition in the school building & the campus as per norms prescribed by Central/ State/U.T. Govt.

The certificate is valid till 31-03-2026

Signature with Seal:

Name:

Designation:

Sub Division Engineer
Water Supply & Sanitation Sub Division
Jalalabad (w)

Name and Address of the Office / Department :

Sub Division Engineer Water Supply & Sanitation Sub Division Jalalabad (w)
Distt - Fazilka.

To

**Glorious convent school,
Mandi Ladhuka
District: Fazilka, State: Punjab**

Note: The certificate is to be issued by authorized officer / PHED Lab / Local Bodies

DISTRICT WATER TESTING LABORATORY, FAZILKA

Village Panchawali, Fazilka
dwtlfazilka@gmail.com

TEST REPORT						
Name & Address of Customer : GLORIOUS CONVENT SCHOOL MANDI , LADHUKA, DISTT-FAZILKA(PUNJAB) Jalalabad			Customer Reference No.		No : 214 Dated -14/04/2025	
			Sample Submitted by		RISHABH BAJAJ	
			Date of sample		14/04/2025	
			Analysis completion Date		16/04/2025	
Discipline : Chemical Testing			Group: Water			
ULR No.:				Sample Type :		Water
Test Report No.:		DWTL/FZK/2496		Date of Issue :		06/05/2025
Registration no.:		DWTL/REG/4963		Condition of Sample :		Unsealed
Collection Point:		Treatment Plant (RO/CWPP/ARP/HH Purifier)		Quantity/Type of Bottle:		1000 ml / Plastic Bottles
Scheme/Source:		Not Mentioned(Not Mentioned)		Location/Depth :		GLORIOUS CONVENT SCHOOL ,MANDI LADHUKA, FAZILKA (PUNJAB) NA
Village :		Ladhuka		Habitation :		Ladhuka
Block:		Jalalabad		District :		Fazilka
Latitude :		Not Mentioned		Longitude:		Not Mentioned
Sr. No	Parameter	Result	As per IS-10500:2012 (2nd Rev.)		Unit	Reference Method :
			Acceptable Limit	Permissible Limit		
1	pH	6.32	6.5-8.5	No Relaxation	--	IS 3025 (Part 11-2024) Electrometric Method
2	Colour	1	5	15	CU	IS 3025(Part 4-2021) Visual Comparison Method
3	Odour	Agreeable	Agreeable	Agreeable	--	IS 3025 (Part 5 – 2018) (Second Revision)
4	Taste	Agreeable	Agreeable	Agreeable	--	IS 3025 (Part 8 – 2023)
5	TDS	48	500	2000	mg/l	IS 3025 (Part 16-2024) Gravimetric Method
6	Turbidity	BDL	1	5	NTU	IS 3025 (Part 10-2024) Nephelometric Method
7	Alkalinity	16	200	600	mg/l	IS 3025 (Part 23-2024) Indicator Method
8	Hardness	12	200	600	mg/l	IS 3025 (Part 21- 2009)(RA 2019) EDTA Method
9	Calcium	1	75	200	mg/l	IS 3025 (Part 40-1991) EDTA Titrimetric Method
10	Magnesium	1	30	100	mg/l	APHA (24th Ed.2024) Method: 3500-Mg+2 B By Calculation Method

DISTRICT WATER TESTING LABORATORY, FAZILKA

Village Panchawali, Fazilka
dwtlfazilka@gmail.com


11	Chloride	6	250	1000	mg/l	IS 3025 (Part 32-1988) Argentometric Method
----	----------	---	-----	------	------	---

Note: Detection Limit(Turbidity:0.5,)

This Report is issued under the following terms & Condition :

1. The results apply to the sample as received only.
2. The sample will be destroyed after retention time unless otherwise specified specially.
3. This report is not to be reproduce wholly or in part and can't be used be as evidence in court of law.
4. Abbreviation used (TDS = Total Dissolved Solids, mg/l = milligram per liter, BDL = Below detection limit, APHA = American Public Health Association, IS = Indian Standard, NT = Not Tested, NA = Not Applicable NTU = Nephelometric Turbidity Unit, RA = Reaffirmed), ND=Not Detected
5. * Value not available or test not performed for this parameter.
6. Temperature condition limit: $25 \pm 5^{\circ}\text{C}$ and Humidity condition limit: $50 \pm 20\%$

Reviewed and Approved By



Mr. Pardeep kumar
Quality Manager
Authorized Signatory
For, District water Testing Laboratory
Fazilka

----- End of the Test Report -----